

**PASCHIM GUJARAT VIJ COMPANY LIMITED****CIRCLE OFFICE : BHAVNAGAR****Schedule - B (To be submitted in separate cover)****Name of work :- Misc. civil work in P/H Compound behind circle office,PGVCL, Bhavnagar**

<b>Sr. No.</b>	<b>Description</b>	<b>R &amp; B SOR Reference 2015-16</b>	<b>Estimated Qty</b>	<b>Rate S.O.R-15-16</b>	<b>Per</b>	<b>Amount</b>
1	Providing & Alluminium Composite Panel of ALSTRONG or equivalent brand with approved shade of 4mm thick, The composite panel should be made of 4mm thick 100% virgin polythene core of LDPE sandwiched between two skins of Alluminium sheet of which one side is having three layers of PVDF coating with Kyanar 500 paint to ensure the supeior corrosion resistance and weatherability and the other side is service coated with Epoxy paint (Grey). The adhesive used DUBOND for bonding the two skins which can take 8 to 9 Kg. weight to separate. This includings structural frames for fixing and finishing etc. complete. including providing necessary lettering on paneling as directed by engineer in charge.	R & B SOR Reference 2015-16	43.00	2450.00	Sqm.	105350.00
2	Providing and Fixing steel hand railing for disabled personal with all the necessary fitting for diabled employees as directed by EIC.	Rate Analysis	1.00	15825.00	Job	15825.00
3	Providing and Fixing FRP sheet including all the fixtures and support arrangement,exclusing vertical support as directed by EIC (Vertical support steel will be issued by PGVCL)	17009	45.00	1685.00	Smt.	75825.00
4	Erection of MS channel for vertical support,exclusing cost of material , material will be provided by PGVCL.	Rate analysis	200.00	7.15	Kg	1430.00
						<b>198430.00</b>
						<b>Rs.</b>

**One lakh Ninty Eight Thousand Four Hundred Thirty Rupees only.****I/We are hereby accepted to execute the above work @ ..... above/below than the estimated cost mentioned above.****Signature of the contractor with Rubber stamp****Date:**