



CITY CIRCLE OFFICE - RAJKOT					
SCHEDULE - B					
NAME OF WORK : Waterproofing work at City 1 laboratory and Aji 2 cash collection Rajkot.					
SR. No.	PARTCULARS OF ITEM	QUANTITY	PER	RATE	AMOUNT
1	Dismantling tiled or stone floors including stacking of serviceable material and disposal of unserviceable material from site of work with all lead and lift.	225.00	Smt	30.00	6750.00
2	Demolition and disposal of unserviceable material with all lead and lift. Unreinforced cement concrete.	1.00	Cmt	383.00	383.00
3	Providing cement vata (10Cm x10Cm) size quarter round in cement concrete in C.M. 1:1 including neat cement finishing, watering etc. complete.	95.00	Rmt	17.60	1672.00
4	Providing and laying broken China Mosaic Flooring for terrace using 12mm to 20mm broken pieces of glazed tiles to be laid over cement mortar 1:3 to plain or slope and to be tempered to bring mortar crème out upto surface using white cement including rounding off junctions and extending them up to 15cm along the wall, clearing with water and oxalic acid etc. as directed by EIC.	225.00	Smt	479.00	107775.00
TOTAL				Rs	116580.00
In words: Rs One lacs sixteen thousand five hundred eighty only.					
I / WE HERE BY AGREE TO CARRY OUT ABOVE SAID WORK AT _____% ABOVE / BELOW THE ESTIMATED COST MENTIONED AS ABOVE AND THUS THE AMOUNT OF MY / OUR TENDER COMES OUT TO BE Rs (In words) Rs.					
Signature of contractor with seal			Superintending Engineer (O&M) Circle office Rajkot		