



CIRCLE OFFICE JUNAGADH

SCHEDULE-B

Name of Work: Supply and spreading coarse aggregate in RSO Campus and refitting existing shed in RSO at shapur

Sr No.	PARTCULARS OF ITEM	QTY	RATE	PER	AMOUNT
1	Dismantalling of sheet roofing including ridges, hips, valleys, gutters, etc. stacking of serviceable materials with all lead and any height upto 35mtr-(ii) G.I. Sheet roofing	614.00	33.96	SMT	20851.44
2	Refitting sheet roofing labour charges including ridges, hips, valleys, gutters, etc. stacking of serviceable materials with all lead and any height upto 35mtr-(ii) G.I. Sheet roofing	614.00	25.00	SMT	15350.00
3	Supplying of crushed stone aggregates, chippings etc. of hard stone of following nominal size free of disintrgrated pieces deleteriarious surface dressing etc.) and grading as per I.R.C code (vii) 6mm	80.00	285.00	CMT	22800.00
4	Spreading stone aggregate for rolling and WBM ancluding filling the interstices to required chamber and gradient	80.00	164.85	Cmt	13188.00
5	Supplying of Scrren of coarse clean sharp sand at site	477.00	187.95	CMT	89652.15
6	Spreading stone aggregate for rolling and WBM ancluding filling the interstices to required chamber and gradient	477.00	164.85	Cmt	78633.45
7	Labor charges for Fabrication of Support structure for,framed work including with cutting Welding as director by EIC, Including Oil painting & All miscellaneous items like bolt, nut, welding rod etc. All required main structural (Girders, Channels , Angle , Flat & Round Bars) material will be provide by PGVCL .	500.00	15.30	KG	7650.00
8	Providing corrugated G.I. Sheets Class-3 roofing fixed with Galvanied iron 'J' or 'L' hooks bolts and nuts 8 mm. diameter with bitumen and G.I.Limpet washers filled with white lead complete excluding the cost of purlins, raffers and trusses. (I) 0.60 mm. Thick sheet	72.00	697.00	sqm	50184.00
Estimated TOTAL RS					298309.04
Bidder's Offer (B)					%Above
Net Amount					%Below

Signature of Contractor

**SUPERNTENDING ENGINEER
PGVCL CIRCLE OFFICE,JUNAGADH**