



CIRCLE OFFICE JUNAGADH

SCHEDULE-B

Name of Work: Providing and Laying paver block in patan sub division office building ground under veraval division.

Sr No.	PARTCULARS OF ITEM	QTY	RATE	PER	AMOUNT
1	P/L cement concrete 1:3:6(1 CEMENT: 3-Coarse sand: 6 - Hand broken stone aggregate 40MM nominal Size) and curing complete excluding the cost of formwork in.- Foundations and plinth.	70.00	2316.60	CUM	162162.00
2	Providing & Fixing Pre-Cast Rubber Dye Interlocking concrete Blocks 60mm thick with grade of concrete M-200 pneumatic compressed by mechanically pressed and as per approved design including 75mm sand layer for levelling and filling the joint with sand in proper linr and level etc. complete of approved manufacture as per the direction of Engineer-in-charge.	178.00	603.00	SQM	107334.00
3	Earth work in cutting including preparing the slope and chamber and stacking ar utilising the cutting stuff in bank as directed upto 200 meters from the endof cutting with all lead and lift.(l) Hard murrum	28.00	163.80	SMT	4586.40
4	White stone bela masonry block in course in foundation and upto plinth with stone of approved quality in cement mortar 1:6 (1cement : 6 course sand) including racking the joints etc. complete.	6.00	3894.20	CUM	23365.20
Estimated TOTAL RS					297447.60
Say Amount					297450.00
Bidder's Offer (B)				%Above	
				%Below	
Net Amount					

Signature of Contractor

**SUPERNTENDING ENGINEER
PGVCL CIRCLE OFFICE,JUNAGADH**