



CIRCLE OFFICE JUNAGADH

SCHEDULE-B

Name of Work: Construction of CC Road for Weighbridge in RSO, Shapur

Sr No.	PARTCULARS OF ITEM	QTY	RATE	PER	AMOUNT
1	P/L cement concrete 1:3:6(1 CEMENT: 3- Coarse sand: 6 - Hand broken stone aggregate 40MM nominal Size) and curing complete excluding the cost of formwork in.- Foundations and plinth.	21.00	2316.60	CUM	48648.60
2	Constructing 10 cm thick Controlled cement concrete M- 200 Grade with Trimix flooring with power trowling sheet form work with M.S. channels, sringing of fair hardness, Non oxidzing, Non metallic, heavy duty floor hardner of FOSROC or equivalent at the rate of 500 g./Sq.M. with 10 mm x 10 mm size groove cutting in concrete as constructution joint and 12 mm thick premix expansion joint at every 20 Meter lengthwith necessary equipments, labors as per design etc. Complete.	210.00	508.00	SQM	106680.00
3	Providing TMT Bars confirming FE 500/500D for R.C.C. work including bending, binding and placing in position complete for G.F.	945.00	71.71	KG	67765.95
4	White stone bela masonry block in course in foundation and upto plinth with stone of approved quality in cement mortar 1:6 (1cement : 6 course sand) including racking the joints etc. complete.	19.50	3894.20	CUM	75936.90
Estimated TOTAL RS					299031.45
Say amount					299040.00
Bidder's Offer (B)				%Above	
				%Below	
Net Amount					

Signature of Contractor

**SUPERNTENDING ENGINEER
PGVCL CIRCLE OFFICE, JUNAGADH**